Nora-Northside Community Council

91st & College Property

February 6, 2020



Referendum Facts & Information Sessions

All Information Sessions Open to the Public

*RSVP required due to space limitations and for our planning **February 20**, 7:00-8:00 PM @ Nora Library 8625 Guilford Avenue

February 24, 7:30-8:30 AM @ CEC 8550 Woodfield Crossing Blvd.

March 5, 7:00-8:00 PM @ CEC 8550 Woodfield Crossing Blvd.

March 9, 7:30-8:30 AM @ CEC 8550 Woodfield Crossing Blvd.

March 18, 12:00-1:00 PM @ Michigan Rd. Library 6201 N. Michigan Road

March 20, 12:00-1:00 PM @ Glendale Library 6101 N. Keystone Avenue

April 8, 5:00-6:00 PM @ CEC 8550 Woodfield Crossing Blvd.





317-205-3332 ext 77200 or mwilson@msdwt.k12.in.us



Next NCC Presentation

Nora-Northside Community Council

Referendum Facts and Information

April 2, 2020








New Construction of Northview Middle School

MS Site Plan

Site Development Timeline

Design & Approval timeline for Referendum Projects





Referendum

Conceptual Layout of Project

Pre-Referendum Planning

Review of available site information:

- Comprehensive plan
- Zoning
- Topography/Drainage patterns
- Vegetation/Wetlands
- Roadway/Pedestrian access
- Utilities

Conduct Traffic & Environmental Study

Conceptual layout of property

Evaluation of total project costs

Community discussions & presentations

- Community Collaboration Meetings
- Nora Community Council
- Individual Discussions
- New Middle School Task Force

Design & Engineering of Project Post-Referendum Design & Construction

PD

FD

Preliminary & Final Design Phases will include a scheduled series of input meetings & collaboration work sessions with end user & community representatives. This would include the New Middle School Task Force.

• During this time there will be continued discussions & presentations with Nora Community Council

CD

Construction Documentation Phase that upon review and approval of concept the project moves into engineering of the design

End of Construction Documentation Phase is when:

- Completed site engineered drawings are submitted for DMD Approval
- Completed drainage/entrance plans are submitted for City Approval
- Completed architectural & engineering drawings are submitted for State & City Approval
- Project is Publicly Bid for Construction

BID

CD

To begin the Construction Phase the contractor uses DMD approval & drainage approvals to obtain an Improvement Location Permit to be able to begin the process of building the project

Referendum

Current Site Investigation

Traffic Study - In process









Current Site Investigation

- Environmental Ecological Study Completed Plant Communities, Soils, Heritage Trees, Invasive Plants, Wetlands and Streams
 - Study allows for insight into eco-friendly design opportunities




91st and College Property Wetlands and Streams





8685 W. Vernal Pk. Bloomington, IN 47404 (812) - 876 - 7711


91st and College Property All Heritage Trees







91st and College Property Soil Types





Soil Types

MUSYM CrA MmB2

Munsell Symbol

ThrA YbvA

YclA

YmsB2




91st and College Property Plant Communities








91st and College Property Invasive Plants







Drainage & Flooding Concerns - Current Site Investigation

Significant erosion currently at the outfall of the Holly Creek Regional Basin














New Construction of Northview Middle School

MS Site Plan

Programming & Building Utilization





- Middle School Enrollment Capacity
 - All three Middle Schools are planned for the same capacity of 1050 at each building.
 - Each Middle School enrollment capacity includes a growth factor which allows for shifting enrollment as demographics throughout district shift.
 - The determination of utilizing the 1050 middle school design capacity came out of the demographic study completed in 2015.
- The district has created Educational Specification for all elementary and secondary schools. The Educational Specifications create accountability for equitable building and sites for all students throughout the district.



Drainage & Flooding Concerns - Amount of Parking/Hard Surface

Preliminary site parking & hard surface layout to be equitable to Eastwood and Westlane Middle Schools.

- 250 car parking and drives
- 30 bus drop-off/pick-up spaces and drives
- Use of existing site parking area for event parking
- Building perimeter circulation and fire lanes
- Site internal pedestrian pathways/sidewalks
- Site perimeter pedestrian pathways/sidewalks as required by code
- Surface associated with 6 tennis courts, baseball, softball, soccer, football field and running track access paths or pads.
- Surface associated with Middle School Building Pad

Above hard surface components could range between 25-30% of total site acreage. - Note that this includes the building in which a portion of it will be 2 stories for footprint efficiencies.





Construction of Northview Middle School

MS Site Plan

91st & College - DRAFT Plan 1/31/2020



Q&A

